

Annexure II

Sr No	Particular	Quantity	Unit	Rate	Amount
A	PAINTING WORK :				
	Brands : Asian paints / ICI / SHERWIN Willams / BENJIMIN MORE / Nerolac				
	All quantities are approximate and may vary to any extent				
1	Providing White/colour washing to ceilings, walls at all heights, with best quality lime colouring material including preparing the surface, sand papering, filling up the crevices with putty, cleaning, scaffolding etc. complete as per specifications.all complete upto the satisfaction of client / arch / engg.				
(i)	White washing 3 coats.	350.00	SQM		-
(ii)	Extra additional coat if required for item above if	100.00	SQM		-
(iii)	White washing with coloured pigments 3 coats.	100.00	SQM		-
(iv)	Extra additional coat if required for item above if required by client and not for the defective or improper finish of the contractor.	100.00	SQM		-
2	Providing Oil bound distemper/ Plastic paint on new work of approved shade & make in 2 or more coats over a coat of primer, putty (2 coats) etc. on sponge finish or smooth finish including preparation of surfaces, sand papering, filling up crevices, leveling etc., finished to desire shade all complete as per specifications & as directed.all complete upto the satisfaction of client / arch / engg.				
(i)	Oil bound distemper.	350.00	SQM		-
(ii)	Extra additional coat if required for item above if required by client and not for the defective or improper finish of the contractor.	100.00			-
(iii)	Plastic paint	350.00	SQM		-
(iv)	Extra additional coat if required for item above if	100.00	SQM		-
V)	Extra for item F2 if BIRLA PUTTY is used instead of	350.00	SQM		-
3	Providing Luster paint on new work of approved shade & make in 2 or more coats over two alternate coats of primer and lambi, etc. on sponge finish / POP smooth finish / over textured finish including preparation of surfaces, sand papering, filling up crevices, leveling etc., finished to desire shade all complete as per specifications & as directed.all complete upto the satisfaction of client / arch / engg.	4000.00	SQM		-
(i)	Extra additional coat if required for item above if required by client and not for the defective or improper finish of the contractor.	300.00	SQM		-

4	Providing Luster paint with hand made texture effect (wooden wenge effect) on new work of approved shade & make in 2 or more coats over two alternate coats of primer and lambi, etc. POP smooth finish / ply including preparation of surfaces, sand papering, filling up crevices, leveling etc., finished to desire shade similar to the mock up room all complete upto the satisfaction of client / arch / engg .	350.00	SQM		-
5	Providing & applying 3 coats of waterproof cement paint of approved shade & make like `Supersnow Cem' Nitco Cem or equivalent to external walls, filling up crevices curing, scaf-folding etc. all as per specifications and as directed (out of 3 coats, one coat will be of Birla white cement.)all complete upto the satisfaction of client / arch / engg. ALL INCLUSIVE OF SCAFFOLDING UP TO ANY HEIGHT.	6000.00	SQM		-
6	Providing & painting 2 or more coats of <u>Synthetic enamel paint</u> of approved make & shade over a approved coat of primer preparing the surface, cleaning scaffolding etc. complete (Areas other than included in respective items)all complete upto the satisfaction of client / arch / engg.				
(i)	Over plastered surface	350.00	SQM		-
(ii)	Over MS or GI piping (less than 50mm dia) & minor structural member (wt less than 4.5kg. per mtr.)	450.00	RM		-
(iii)	Over MS or GI piping (above 50mm dia)	0.00	SQM		-
(iv)	Over structural steel, built-in sections MT	0.00	KG		-
7	MS GRILL WORK				
	Appx.quantity for MS Grill work at IIP-Ahmedabad.	100.00	Sq.Mtr.		
TOTAL : Rs.					-