

**FINANCIAL BID:
EOI FOR INTERNAL AND EXTERNAL PLASTER REPAIRING, PAINTING AND
ELECTRICAL WORK IN OLD BOYS HOSTEL, IIP - MUMBAI**

S.No.	Particulars	Units	Qty.	Rate	Amount
A	External painting work (student hostel)				
1	Scaffolding for exterior paint	Sq. Ft.	15000		
2	Acrylic Emulsion Exterior Paint (ICI, Asian Paint Apex)	Sq. Ft.	18000		
B	Internal Painting work (Student Hostel)				
	Providing and applying internal painting in smooth finish with three coats by brush and roller. The base surface is to be cleaned thoroughly of dirt, dust and mortar drops etc. and it is to be applied with primer and/or two coats of paint is to be applied wherever required considering the type of paint job on all surfaces, as per the instruction and specifications of the including the cost of all the corresponding materials, scaffoldings etc. complete.				
1	Oil paint for grills and doors (Asian Paints, ICI)	Sq. Ft.	3500		
2	Acrylic Plastic Paint (Asian Paint, ICI)	Sq. Ft.	25000		
C	Plastering work				
	Providing internal cement plaster 6mm thick in a single coat in cement mortar 1:4 without neeru finish to concrete surface in all position including scaffolding and curing etc. complete.	Sq. Ft.	800		
	Note: - Providing internal plaster as gypsum plaster (optional)				

	Providing internal cement plaster 10 mm thick in a single coat in cement mortar 1:4 without neeru finish to concrete or bricks surface in all position including scaffolding and curing complete.	Sq. Ft.	1000		
	Note : Providing internal plaster as gypsum plaster (Optional)				
	Water saving measure shall be used during curing.				
D.1	Construction of Old toilet and bathrooms				
	including brick missionary, plaster, tiling work, fittings (shower point, tap point x 1, cock x1, geyser point x 1 and electrical work	Nos.	6		
D.2	Repairing of Old toilet and bathrooms				
	(supply of geyser 3ltrs. Fitting, electrical works, damaged tiles)	Nos.	6		
E	Sliding work				
	Dismantling and supply, erection of 3 roll track anodized, 6 mm glass, mosquito net and fittings etc.	Sq. Ft.	300		
F	MS Grill	Kgs.	1200		
G	Brick missionary work for Balcony area	Sq. Ft.	350		
H1	Electrical work in student rooms and passage area for boys hostel				
	(Supply and erection 20/24 watts LED bulb 2 Nos. and all switch and socket replacement.	Lumpsum	1		
H2	Electrical panel (supply and erection for 440 V Electrical panel)	Nos.	2		

H	Water proofing for terrace area	Sq. Ft.	6500		
	TOTAL				

Seal of the firm

(Signature of Authorized Representative)

Date :

Place :